CENTERLINE PLAT
HOCKING COUNTY, GREEN TOWNSHIP
SECTIONS 27 & 33, T.13N., R.16W.

CALC. BY: C.S.G. DATE: 1-6-93	HOC-328-10.51		OHIO	31/36
CHK'D: BY: DATE:			FHWA 5 REGION	1/6
FEDERAL PROJECT	STP-916 (3)	STATE PROJECT	10 8 9 0 0	

PID - 10209

SCALE
0 50 100
1 INCH = 100 FEET

IPF&U
568+26.08
448.48'

IPF&U
570+63.25
216.85'

CURVE DATA
PI = STA. 560+29.24
△ = 44° 21' 09.9" LT.
DC = 05° 00' 00"
R = 1145.92'
L = 887.06'
T = 467.09'
Ex. = 91.54'

IPF&U
567+74.79
42.41'

END ACQUISITION
STA. 567+25.00

N 39° 41' 28" W

565

PT 564+49.21

END PROJECT
STA. 566+50.00
STP-916 (3)
S.L.M. 10.73

S.L.M. 10.51
BEGIN PROJECT
STA. 555+00.00
STP-916 (3)

BEGIN ACQUISITION
STA. 553+80.00

PC 555+62.15

560

EX SR 328

SECTION 33
SECTION 32

SECTION 27
SECTION 26

CALC. CORNER

S 04° 34' 18" W - 1395.88' TO ℄ STA. 557+68.67

SECTION 33
SECTION 27

553

N 04° 39' 49" E

555

℄ SURVEY & CONSTRUCTION S.R. 328

S 04° 34' 18" W
℄ STA. 557+68.67

SECTION 33
SECTION 27

IPF&U
549+78.71
17.29' LT.

IPF&U
551+76.69
17.61' LT.

IPF&U
549+76.71
420.60'

IPF&U
551+80.74
420.26'

ITEM 604, CENTERLINE REFERENCE MONUMENTS, SHALL BE SET BY THE CONTRACTOR AS SHOWN ON THESE PLANS, DURING CONSTRUCTION. THE MONUMENTS WILL HAVE AN ACCURACY OF + OR - 0.02 FT. THE MONUMENTS WILL BE SET UNDER THE DIRECTION AND SUPERVISION OF THE DISTRICT 10 SURVEY SUPERVISOR.

NOT STATE PLANE COORDINATES

STATION	COORDINATES	
S.R. 328	NORTHING	EASTING
P.I. 552+68.00	199895.1410	199992.1270
P.C. 555+62.15	200188.3228	200016.0437
P.I. 560+29.24	200653.8650	200054.0210
P.T. 564+49.21	201013.2996	199755.7282
P.I. 567+26.55	201226.7160	199578.6150

RECEIVED _____, 19__
RECORDED _____, 19__
BOOK _____, PAGE _____
_____
COUNTY RECORDER

I HEREBY CERTIFY THAT THIS IS A TRUE DELINEATION OF A SURVEY MADE FOR THE OHIO DEPARTMENT OF TRANSPORTATION IN 1991.

_____ DATE
_____ REG. SUR. NO. _____
SIGNED _____
DATE _____ DISTRICT DEPUTY DIRECTOR

SEAL

CONCRETE MONUMENTS TO BE SET RIGHT AND LEFT OF CENTERLINE AT THE FOLLOWING LOCATIONS DURING CONSTRUCTION OF S.R. 328.

STATION	RT.	LT.	STATION	RT.	LT.
POT 553+00.00	25'	25'			
PC 555+62.15	25'	20'			
POC 558+50.00	20'	25'			
POC 562+00.00	25'	25'			
PT 564+49.21	20'	20'			
POT 566+50.00	20'	20'			

NOT TO SCALE
FOR INFORMATION ONLY



REV.	DATE	DESCRIPTION
	FILING DATE	2-11-93

CENTERLINE PLAT