| SHEET NUMBER | | | | | | | | | | | PARTICIPATION | | ITEM | ITEM EXT. | GRAND TOTAL | UNIT | DESCRIPTION | SEE SHEET NO. |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 6 | 7 | 8 | 12 | 13 | 16 | 21 | 28 | 32 | 34 | | | | | | | | | |
| | | | | | | | | | | | | | | | | | TRAFFIC CONTROL | |
| | | | 4 | 4 | | | | | | | | | 621 | 54000 | 8 | EACH | RAISED PAVEMENT MARKER REMOVED | |
| | | | 8 | 8 | | | | | | | | | 626 | 00100 | 16 | EACH | BARRIER REFLECTOR | |
| | | | | 7 | | | | | | | | | 630 | 02100 | 7 | FT | GROUND MOUNTED SUPPORT, No. 2 POST | |
| | | | 4 | 4 | | | | | | | | | 630 | 84900 | 8 | EACH | REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL | |
| | | | | 1 | | | | | | | | | 630 | 85100 | 1 | EACH | REMOVAL OF GROUND MOUNTED SIGN AND REERECTION | |
| | | | 4 | 1 | | | | | | | | | 630 | 86002 | 5 | EACH | REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL | |
| | | | 0.06 | 0.15 | | | | | | | | | 642 | 00090 | 0.21 | MILE | EDGE LINE | |
| 1.6 | | | 0.03 | 0.08 | | | | | | | | | 642 | 00290 | 1.71 | MILE | CENTER LINE | |
| | | | | | | | | | | | | | | | | | FOR STRUCTURE HOC-328-0271 SEE SHEET 23 OF 45 | |
| | | | | | | | | | | | | | | | | | FOR STRUCTURE HOC-328-593 SEE SHEET 36 OF 45 | |
| | | | | | | | | | | | | | | | | | MAINTENANCE OF TRAFFIC | |
| | 4 | | | | | | | | | | | | 614 | 12338 | 4 | EACH | WORK ZONE IMPACT ATTENUATOR (BIDIRECTIONAL) | |
| | 11 | | | | | | | | | | | | 614 | 13302 | 11 | EACH | BARRIER REFLECTOR, TYPE B2 | |
| | 11 | | | | | | | | | | | | 614 | 13360 | 11 | EACH | OBJECT MARKER, TWO WAY | |
| | 0.28 | | | | | | | | | | | | 614 | 22000 | 0.28 | MILE | WORK ZONE EDGE LINE, CLASS I | |
| | 30 | | | | | | | | | | | | 614 | 26000 | 30 | FT | WORK ZONE STOP LINE, CLASS I | |
| | 190 | | | | | | | | | | | | 622 | 40020 | 190 | FT | PORTABLE CONCRETE BARRIER, 32" | |
| | 20 | | | | | | | | | | | | 622 | 40040 | 20 | FT | PORTABLE CONCRETE BARRIER, 32", BRIDGE MOUNTED | |
| | | | | | | | | | | | | | 614 | 11000 | LUMP | | MAINTAINING TRAFFIC | |
| | | | | | | | | | | | | | 619 | 16010 | 8 | MONTH | FIELD OFFICE, TYPE B | |
| | | | | | | | | | | | | | 623 | 10000 | LUMP | | CONSTRUCTION LAYOUT STAKES | |
| | | | | | | | | | | | | | 624 | 10000 | LUMP | | MOBILIZATION | |

CALCULATED JAMW
CHECKED SWL

GENERAL SUMMARY

HOC-328-2.70/5.93

11
45