COUNTY OF HOCKING, SALT CREEK TWP
SEC. 24, T. 11 , R. 19

CALC. BY G.P.S. DATE 3/87			OHIO
CHK'D BY JEL DATE 3/87	HOC-56-6.99		HWY REGION 5
FEDERAL PROJECT	BRS-823 (5)	STATE JOB NO.	105330

35/35 — 4/4

R/W PLAN PART II

Scale in Feet: 0 50 100

Cultivated

BRUCE H. & JANICE M. EBERT (13) 3-T 1.276 AC.

T & D PROPERTIES

NOTE: T & D Properties Have a Limited Easement for Access to Their Property at the Existing Drive Left of Station 374+00 ±.

Sta 370+13.13 256.14' Lt.

I.P. fnd.

(14)

Dirt Field Dr.

Wooded

Pasture

Dirt Field Dr.

Sta 373+47.19 99.73' Lt.

Sta. 374+76.84 81.14' Lt.

(13-T)

P.C. 71+65

P.T. 72+97.01

371+80.16 95' Lt.

I.P. fnd

P.C. 74+21.51

N.W. 1/4 SECTION 24

N.E. 1/4 SECTION 24

(13)

I.P. fnd 374+75.76 55' Lt.

374+74.73 30' Lt.

End Work Sta 375+49.47

P.T. Temp. Rd. Sta. 75+53.52 = S.R. 56 Sta. 375+49.47

R/W 374+73.50

Begin Work Sta. 363+35.00

361+17.28 30.00' Lt.

N. 3° 05' 50" E

30'

30'

361+22.58

R/W

362

P.C.C. Temp. Rd. Sta. 63+33.87 = S.R. 56 Sta. 363+35

364+00 30.00' Lt.

P.T. 65+34.75

P.C. 66+58.55

Temporary R/W

Temporary Road Construction Limits

℄ Temporary Road

368+00 115' Lt.

P.T. 67+57.00

Sycamore

Maple

℄ Temporary Road

Temporary Road Construction Limits

Const. Limits

Brush

Const. Limits

R = 2173.68'

R/W

50'

40'

30'

℄ N 88° 45' 00" E 368' Survey

U.G. Tele.

S.R. 56

Grass Field Dr.

Gravel

Const. Limits

SLM 7.04 End Project Sta. 371+43.94

BRS-823 (5)

374+72.26 30' Rt.

374+80.08 P.K. Fn'd O.D.O.T #205

360+89.35 P.K. Fn'd ODOT #101

Ex. P.C. 361+05.75 P.K. Set

361+22.71, 0.74' Rt. R.R. Spike Fn'd.

Exist. P.I. I.P. Fn'd

CURVE DATA, EXIST. S.R. 56

P.I. Sta. 363+89.35
Δ = 14° 40' 00"
Dc = 2° 36' 00"
T = 283.60'
Lc = 564.10'
R = 2203.68'
E = 18.17'

Begin R/W Acquisition Sta. 364+00

Ex. P.T. 360+69.85 P.K. Set

P.K. Fn'd. Sta. 368+54.25 S.R. 56 = Sta. 10 + 00.00 C.R. 184

SLM 6.99 Begin Project Sta. 368+77.06

BRS-823 (5)

369+27.12 40' Rt.

369+80.16 95' Rt.

371+80.16 95' Rt.

Construction Limits

Asphalt

℄ 40' C.R. 184

12-T

Salt Creek

12"G

10"G

#513-10" H.P.

#423-10" H.P.

ALVIN L. & ANNE L. ARLEDGE (12) 2-T 0.282 AC.

#C18-12" H.P.

End R/W Acquisition Sta. 374+74.73

N. 1° 06' 32" E 451.05' QUARTER SECTION LINE

GORDON S. & MARTHA L. McKEE (11)

Cultivated

Sta 361+82.68 425.68' Rt.

I.P. Fn'd

Dirt

Dirt Field Dr.

R/W

R/W

℄ Gravel

S. 48° 34' 00" E Narrows Rd.

Sta 374+54.93 450.66' Rt.

I.P. Fn'd

QUARTER SECTION LINE N.W. 1/4 SECTION 24 S.W. 1/4 SECTION 24

Completion Date 9-3-87

UTILITIES NOTE:
The locations of the underground utilities shown on these plans are as obtained from the owners of the utilities as required by Section 153.64 Ohio Revised Code.

REV.	DATE	DESCRIPTION
F.B	1-20-88	Added Part II & Changed Parcel Nos.

RIGHT OF WAY STA. 361+00 TO 376+00